



**MADHYA PRADESH POLLUTION CONTROL BOARD**

**Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016**

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

## **E-Tender Notice**

**NO. MPPCB/HO/MAINT./TS/01/2021-2022**

## **TENDER DOCUMENT**

**FOR**

## **Renovation of Conference Hall & Other Work at MPPCB, Bhopal**



**Year: 2021-2022**

---

### **M. P. Pollution Control Board**

E-5 Sector, Paryawaran Parisar, Arera Colony, Bhopal – 462016

PBX : +91(0755) / 2466191, 2517628

Web: [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

E. mail: [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) , [rpt\\_74@rediffmail.com](mailto:rpt_74@rediffmail.com)



## **MADHYA PRADESH POLLUTION CONTROL BOARD**

**Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016**

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

### **NOTICE INVITING E-TENDER**

#### **E-TENDER NOTICE NO. MPPCB/HO/Maint/TS/01/2021-22**

E-Tenders are invited in two bid system from reputed / registered Contractor for Renovation of conference hall and other work at M.P. Pollution Control Board, Bhopal of Estimated cost of Rs. 63,12,765.00 (Rupees Sixty three Lakh Twelve Thousand Seven Hundred Sixty Five only) on the portal at <http://www.mptenders.gov.in> . The Tenders shall be received till 04/09/2021 up to 03:00 PM and the First Cover (Technical Bid) shall be opened on dated 06.09.2021 at 3:00 PM. For further details please refer web site at [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in) and [www.mptenders.gov.in](http://www.mptenders.gov.in)

**Executive Engineer  
(Maintenance)**



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

## NOTICE INVITING TENDER

### TENDER NOTICE NO. MPPCB/HO/Maint/TS /01/2021-22

- (1.1) The Member Secretary, M. P. Pollution Control Board invites E-Tenders on portal at <http://www.mptenders.gov.in> from reputed / registered Contractor for Renovation of conference hall and other work at M.P. Pollution Control Board, Department of Environment, Govt. of Madhya Pradesh of in two cover system (Technical and financial) for the following details:

Sl. No.	Description of Items	Qty.	Estimated Cost (Rs.)	Earnest Money (EMD) (Rs.)
1	Renovation of conference hall such as false ceiling, work station, tiles , granite work, wall painting, ply & mica work , Electrical wiring, modular switch socket, LED lights, Air Conditioners, Net, telephone line and installation of public addressing system complete works etc.	As per BoQ	63,12,765.00  (Rupees Sixty three Lacs twelve thousand seven hundred sixty five only)	1,26,255.00

- (1.2) Tender documents may be downloaded from Government of Madhya Pradesh E-Procurement portal at <http://www.mptenders.gov.in> as per the schedule given in Critical Date Sheet as under:

### CRITICAL DATE SHEET

Description	Date	Time
Date of Publishing	06.08.2021	3:00 PM
Bid Submission Start Date	13.08.2021	3:00 PM
Bid Submission End Date	04.09.2021	3:00 PM
Technical Bid Opening Date	06.09.2021	3:00 PM
Financial Bid Opening Date	Will be informed later	

- (1.3) The proof for submitting Tender Cost of Rs. 2500.00 (Rupees Two Thousand Five Hundred only) and Earnest Money Deposit (EMD) of an amount of Rs. 1,26,255.00 (Rupees One Lakh Twenty Six Thousand Two Hundred Fifty Five only) shall be submitted online on or before the last date of submission of tenders. No tender shall be considered without requisite tender fee and earnest money. (No any exemptions entertained by Board).
- (1.4) The Tender documents will not be available in physical form. The detailed terms & conditions are available in tender document. For detailed tender document and any amendment (if required) regarding the said tender shall be available on Board's Web site [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in) and [www.mptenders.gov.in](http://www.mptenders.gov.in).

**Executive Engineer  
Maintenance**



## MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it mppcb@rediffmail.com](mailto:mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

### TENDER NOTICE NO. MPPCB/HO/Maint/01/2021-22

#### GENERAL CONDITIONS

E-Tenders are invited from eligible contractors for the Renovation of conference hall and other work at MPPCB, Bhopal as per date schedule described in NIT on item rate basis in two bid system. The tenders are to be submitted in two covers i.e First Cover (Technical Bid) and Second Cover (Financial Bid in BoQ templet).

- (1) Procedure for Submission of the Tender: Each bidder shall submit his offer in two Covers. First Cover shall contain scanned copies of proof for submitting Tender Cost and Earnest Money (EMD) online in the portal along with all qualification documents such as Documents indicating the set up of organization, Partnership, Proprietorship, Pvt. Ltd, public ltd. etc., Valid Enlistment with MPPWD/ CPWD/MES/Railways/Public Sector Undertakings, other Government bodies etc. Details of works of similar nature carried out in Central or State Government bodies/departments, Public Sector Undertakings (if any). Copy of valid GST Number, Copy of Registration with Employees Provident Fund Organization, CA certificate for turnover and List of permanent employees. The Second Cover shall contain financial offer (BoQ). The tender shall be submitted online in two covers as per following details:
- (a) **First Cover (Technical Bid)** should contain scanned copy of proof for submitting Tender Cost and Earnest Money (EMD) online in the portal along with all qualification documents. The first cover must contain self verified scanned copies of the following documents:
- (i) Scanned copies of proof for submitting Tender Cost and Earnest Money (EMD) online in the portal.
  - (ii) Checklist duly filled, stamped and signed as per Annexure-2 of the tender document along with entire tender document signed by the bidder on each page as a part of their acceptance.
  - (iii) Documents indicating the set up of organization, Partnership, Proprietorship, Pvt. Ltd, public ltd. etc.,
  - (iv) Valid Enlistment with MPPWD/ CPWD/MES/Railways/Public Sector Undertakings, other Government bodies etc.
  - (v) Details of works of similar nature carried out in Central or State Government bodies/departments, Public Sector Undertakings.
  - (vi) Copy of valid GST Number
  - (vii) Copy of PAN card.
  - (viii) Copy of Registration with Employees Provident Fund Organization.
  - (ix) List of permanent employees for work execution such as Project Manager, Site Engineer (Civil/Electrical), Supervisor with their contact mobile number.
  - (x) CA certificate for last three financial years with UDIN number. The turn over should be more than Rs. 1.00 crore for each financial year.



## MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

- (xi) An undertaking shall be submitted by the bidder, regarding whether they are not black listed in any Govt. organization / institutions.
- (xii) The bidder shall also provide Bank Name, Account Name, Account Number, Account Type, Branch, IFSC Code for safer & easier payment transaction through RTGS/NEFT.
- (b) Second Cover (Financial Bid):** Offers received in due time shall be evaluated technically by a committee constituted by the Competent Authority, M. P. Pollution Control Board and as per the recommendation of committee, depending upon the credentials submitted in second cover, suitability of work with respect to offered Terms & Conditions and documents attached with the technical bid, the financial offer shall be opened. The date of opening of financial bids (Second Cover) will be informed later. Financial Bid shall comprise financial offer in BoQ of the tender document.

### **Instructions to the Bidders on e-tendering:**

- (i) The bidder shall submit their offer in accordance with this tender document.
- (ii) The bidder, after submitting its tender, is permitted to alter/modify its tender so long as such alterations/modifications are done within the deadline for the online submission of tenders. Any alteration/modifications in the tender thereafter is not permitted.
- (iii) No tender can be withdrawn after the deadline for online submission of tender and before expiry of the tender validity period. If a bidder withdraws the tender during this period, it will result in forfeiture of the earnest money furnished the bidder in its tender.
- (iv) Both covers of the tenders will be opened on-line on prescribed date and time. In case the specified date of tender opening falls on / is subsequently declared a holiday or closed day, the tenders will be opened at the appointed time and place on the next working day.
- (v) Physical presence of the bidder at the time of opening of tender will not be essential in the e-tendering process. At the appointed time, the bid openers would open the bids online and the details of the technical bids offered by the bidders would be known to all on the portal.
- (vi) The first cover, i.e. Technical Bids will be opened on-line, first and evaluated by the Committee to assess that the work offered are as per the tender document in Annexure-1, necessary credentials and other relevant documents.
- (vii) The Second Cover, i.e. Financial Bid of only technically qualified offers shall be opened online and evaluated. The date of opening of financial bids (Second Cover) will be informed later.
- (viii) The tender will first be scrutinized to determine whether they are complete and meet the essential and important requirements, as prescribed in the Tender



## MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

Document. The bids, which do not meet the basis requirements, are liable to be treated as non-responsive and rejected.

- (ix) The Board reserves right to accept in part or in full any tender or reject any tender without assigning any reason or to cancel the tendering process and reject all tenders at any time prior to award of contract, without incurring any liability, whatsoever to the affected Bidder or Bidders.
- (x) Financial Bids of the Bidders, whose technical bids are qualified, shall only be opened. The lowest Bidder (L1) shall be determined on the basis of the Price quoted by the Bidder altogether for work related with renovation of conference hall and other work as described in the tender document.
- (xi) The Earnest money deposit (EMD) of Rs.1,26,255.00 (Rupees One lakh twenty six thousand two hundred fifty five only) shall only be submitted through online on the portal and scanned copies of proof for submitting Earnest Money (EMD) online in the portal along with First cover. In the event of the tender being accepted the earnest money shall form a part of the security deposit.
- (xii) The approved firm shall have to submit 7.5% security deposit of the ordered value in the form of bank Guarantee/ FDR in favor of the Member Secretary MPPCB Bhopal, for a period of 24 months; other wise 7.5% amount shall be deducted from the bill. The Bank Guarantee/ FDR or deducted amount shall be released after 24 months on satisfactory performance of the job done.
- (xiii) The tenders shall remain open for acceptance for a period of 180 days from the date of opening of the First Cover.
- (xiv) Rate(s) quoted shall include provision of all scaffoldings, tools, plants, accessories and shifting of office material/ files etc., required for proper execution of the work. Rate(s) shall also cover the cost of handling, carriage, all type of taxes, duties and royalties, etc.
- (xv) **Payment Condition:** The contractor will submit the bill of the work done, these will be verified by the Engineer through the quality and volume of the work executed and recorded in the measurement book/Measurement sheet. The payment of bill shall be made on fulfillment of contractual liabilities.
- (xvi) No advance payment shall make to contractor against material procurement.**
- (xvii) The M. P. Pollution Control Board reserves the right without assigning any reasons therefore to:
- Accept or reject any or all tenders in whole or in part;
  - Increase or decrease the quantities of any item of the work and the successful tenderers shall perform the same at the rates quoted.
- (xviii) Time of completion of work will be four (04) months from the date of commencement as per letter of intent, which can be relaxed for additional 30 days by the Member Secretary. After scheduled time limit, 2% of the total



## MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

contract value per month penalty shall be levied the amount of penalty shall not be more than 10% of the contract value or bill value whichever is more.

- (xix) Any further clarifications may please be obtained from the undersigned. Intending tenderers are encouraged to visit the site of work and acquaint themselves with the scope of work.
- (xx) Price quoted by the tenderer shall be firm, inclusive of all levies, excise duty and GST, any other tax etc. No escalation in price would be permitted on any ground.
- (xxi) TDS and any other taxes as applicable from time to time shall be recovered by the Board from the bills submitted by the contractor. Any change in the rate of TDS shall be to the contractor's account.
- (xxii) The quantity of work may be variable the tenderers are requested to make him familiar with the site and work to be executed.
- (xxiii) Renovation work is to be done as per drawing /map enclosed in the last page of the tender document or as per Engineer In-charge.
- (xxiv) Work defects liability period shall be two years from the date of completion of the work.
- (xxv) The bidder shall provide the list of permanent employee for work execution such as project manager, Site Engineer (Civil/Electrical), supervisor with their contact mobile number.
- (xxvi) This office shall not be responsible for any damage to the machine in case of an accident or otherwise, theft of machine / material and accessories therein. Similarly, this office shall not be responsible for any third party claims. On the other hand, the contractor will be personally liable for any personal injury of their staff or other manpower deployed at MPPCB site.
- (xxvii) In case of any dispute the decision of Chairman, M.P. Pollution Control Board shall be final & binding.
- (xxviii) Material specifications are mentioned against items of the tender. However where no specification is given one of the following make of the material shall be used. The contractor will have to get the sample approved from the Engineer In charge whose decision shall be binding on the contractor. The condition is also applicable for any material not mentioned in the specification or schedule of works no deviations are allowed in these even during / after tender.

SN.	MATERIAL APPROVED	MATERIAL APPROVED BRANDS
1.	Paints	Asian, Berger, Narolac
2.	Putty	JK, Birla, Tata,
3.	False ceiling	Saint-Gobain, Armstrong, diamond ceiling,
4.	Door closer ISI mark	Godrej/Smart
5.	Ply wood	Archid, Green Ply, Century Ply, Black vista.
6.	glass/mirrors	Saint Gobin, Modi Guard.
7.	laminates	Merino, ArchidLam, Green Lam,Optus
8.	veneers	Durian, Green Lam, Archidply, Century
9.	adhesive	Fevicol SH, Araldite, Pidilite
10	hardware fittings	Ebco,Godrej, Ozone, Haffle
11.	acoustic wall panels	Anutone,Armstrong,Saint-Gobain or equivalent
12.	Wooden Flooring	Green Floor, squarefoot, Vista, Action Tesa



## MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

13.	Curtain/blinds.	Vista, Windowtech or equivalent
14.	Aluminium section	Jindal, Maan or Equivalent
15.	Particle Board	Action Tesa, Merino or Equivalent
16.	Vitrified tile	Johnson, Nitco, Oaisis, , Kajaria, Somany
17.	Sanitary fixture	Cera, Hindustan, parryware, Hindware, jaquar,
18.	CPVC/PVC PIPES	Astrol, kisan, Supreme or equivalent
19.	<b>Workstation</b>	Godrej, Methodex, Herman Miller
20.	Chairs/furniture	Godrej, Methodex, Herman Miller
	<b>Electrical Items</b>	<b>APPROVED BRANDS</b>
1.	Air conditioner	Daikin, Voltas, Bluestar,
2.	Wire and copper cable	Havells/Finolex/Anchor/KEI/Polycab
3.	Modular Switches	CPL, Anchor Rome, Legrand
4.	PVC non metallic conduit pipe (casing/casing) with accessories (ISI Mark)	Polycab/Precision/Modi, AKG, Crown,
5.	MCB	Standard Heavels, C&S, Legrand, HPL,
6.	LED lights	Phillips/bajaj/Wipro/Syska/
7.	Light fixtures	Phillips/bajaj/Wipro/Syska/
8.	Wall fan	Bajaj/ Usha/ Heavells
9.	Audio Conference System	AHUJA, BOSCH, CLASSICO
10.	Wall mounted speakers	AHUJA, BOSCH, CLASSICO
11.	Over head projector	Sony or Panasonic Or Benq or Epson
12.	Networking	Dlink or equivalent

**NOTE:** Contractor should obtain approval from engineer in charge of the Board before placing order for any specific material / agencies.

**Executive Engineer  
(Maintenance)**





# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

Annexure-1

## TENDER NOTICE NO. MPPCB/HO/Maint./TS/01/2021-22

### Schedule of Work/Requirement

Name of Work: Renovation of Conference Hall and Other work at MPPCB, Bhopal.

SN.	Item of Work	Unit	Qty
1.	<p>Providing and fixing tiled false ceiling of specified materials of size 595x595mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x 1.6 mm fixed to ceiling with 12.5mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanized butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T sections shall be pre painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. Glass fiber Acoustical Suspended Ceiling System with 16 mm thick tegular edge or micro look edge tiles of size 595x595mm. The tiles should have Humidity Resistance (RH) of 99%, NRC 0.5, Light Reflectance <math>\geq 83\%</math>, Thermal Conductivity <math>k = 0.052 - 0.057</math> w/m K, Colour White Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 and 7) in module size of 600 x 600 x 16mm with Bio Block coating on the face of the tile, suitable for Green Building application, with Recycled content of 38 - 41%. The Tile and grid system used together should give a 15 year warranty. (SOR Item No.12.59.5)</p>	Sqm	180
2.	<p>Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts and bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre to which the ceiling</p>	Sqm	36



## MADHYA PRADESH POLLUTION CONTROL BOARD

**Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016**

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	<p>section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of 10mm thick plaster of Paris (gypsum anhydrous) sheet to ceiling section and perimeter channels with the help of dry wall screws of size 3.5x25mm at 230mm interval including jointing and finishing to a flush finish of tapered and square edges of POP board with jointing compound (POP paste) including the cost of making openings for light fittings, grills, diffusers cutouts made with frame of perimeter channels suitably fixed all complete as per drawing, specifications and direction of the Engineer-in-charge. (SOR Item No - 12.58.1) Flat surfaces.</p>		
3.	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in - charge. In cement mortar. (SOR Item no.- 15.6.3)	Cum	2.0
4.	Dismantling tile/ Kota stone/ Marble / Granite work in floors/walls and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles above 25 mm and upto 40 mm. (SOR NO.15.11.2)	Sqm	230
5.	Dismantling wooden boarding's in lining of walls and partitions, excluding supporting members but including stacking within 50 metres lead: Thickness above 25 mm upto 40 mm (SOR Item No.15.36.3)	Sqm	27.27
6.	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm) with double speed adjustment with necessary accessories and screws etc. complete. (SOR Item No.9.95)	Nos.	5
7. (NON SOR)	Providing & Fixing of Loft Covering Made up of 18mm thick frame work. Loft Cover with Openable Shutters made up of 18mm thick ply finished with 1.0mm thick laminate from outside & 0.8mm thick laminate from inner face of ply. Shutter is fix with the help of hinges. item includes all necessary hardware complete etc. (NON SOR)	Sqm	4
8.	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.	Kg	115



## MADHYA PRADESH POLLUTION CONTROL BOARD

**Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016**

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	(Glazing, paneling and dash fasteners to be paid for separately) : Powder coated aluminium (minimum thickness of powder coating 50 micron) ( SOR Item No. 21.1.1.2)		
9.	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For shutters of doors, windows and ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of Powder coated aluminium (minimum thickness of powder coating 50 micron) ( SOR Item NO. 21.1.2.2)	Kg	28
10.	Providing and fixing 12mm thick Pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides. ( SOR Item No. 21.2.2 )	Sqm	36
11.	Providing & Fixing of glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item) With float glass panes of 5.0 mm thickness (weight not less than 12.50 kg/sqm ) ( SOR Item No. 21.3.2 )	Sqm	25
12.	Providing and fixing aluminium round shape handle of outer dia 100mm with SS screws etc. Complete as per direction of Engineer-in-Charge. Anodized (AC15) aluminium ( SOR Item No. 21.16.1 )	Nos.	8
13.	Providing and fixing Brass 100 mm mortice latch and lock with 6 levers without pair of handles (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete.( SOR Item No. 21.13 )	Nos.	6
14.	Providing and fixing Stainless steel hanging type floor door stopper with necessary screws, etc. complete ( SOR Item No. 9.76 )	Nos.	10
15.	Providing and fixing expandable fasteners of specified size with necessary plastic sleeves and galvanised M.S. screws including drilling holes in masonry work /CC/ R.C.C. and making good etc. complete.60 mm long ( SOR Item No. 9.28.5 )	Nos.	80
16.	Providing & Fixing stainless steel butt hinges (heavy weight) with stainless steel screws etc. complete (125x64x2.50 mm) ( SOR Item No. 9.74.1 )	Nos.	12
17.	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia and length	Cum	0.2



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	(hold fast lugs or dash fastener shall be paid for separately).Sal wood ( SOR Item No. 9.1.2 )		
18.	Providing and fixing 12mm thick panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25mm to 40mm thick. Marine plywood conforming to IS: 710 ( SOR Item No. 9.133.1)	Sqm	55
19.	Providing and Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt / suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S including cost of adhesive of approved quality. 1.0 mm thick. ( SOR Item No. 9.134.2 )	Sqm	24
20 (NO N SO R)	<b>SOFA CENTRE TABLE WOODEN</b> (900mm x 900mm) Providing and fixing Centre table made out of 50mm x 50mm Teak wood legs with outer frame made out of 40mmx75mm second class teak wood with 12mmx12mm groove all around to accommodate 12mm Coloured glass of approved shade on Top.Melamine polish of approved shade & texture on all wooden & veneer surfaces.Work include all labour, material, etc. complete and nothing will be paid extra for execution of the item. All work is to be executed as per the direction and approval of Engineer in charge .( NON SOR)	No.	1
21. (NO N SO R)	<b>SOFA CORNER TABLE WOODEN</b> (600mm x 600mm x 450mm) Providing and fixing Centre table made out of 50mm x 50mm second class Teak wood legs with outer frame made out of 40mmx75mm second class teak wood with 12mmx12mm groov all around to accommodate 12mm Coloured/Plain glass of approved shade on Top. .Melamine polish of approved shade & texture on all wooden & veneer surfaces.Work include all labour, material, etc. complete and nothing will be paid extra for execution of the item. All work is to be executed as per the direction and approval of Engineer in charge .( NON SOR)	Nos.	2
22. (NO N SO R)	Storage Cabinet/overhead cabinet (In Mica)- 450mm deep. Providing & fixing Cabinet - Basic Structure/frame of cabinet is made out of 18mm thick commercial Ply board with 12mm ply on back side to be screwed to the existing position on wall with vertical partition of 18mm ply at centre/ and having horizontal open shelves as per design, supported on S.S. brakets/Fixed on side vertical Boards.All external exposed surfaces of 18mm thick Comm. ply board is to be laminated with 1.0 mm thick laminate & All internal surfaces is finished with o.8mm thick liner laminate of approved quality, make and color. All Edges of Ply Board is to be protected by fixing 6mm thick T.Wood beading/2mm thick PVC Lipping/12mm.thick MDF Board. All exposed T.W. beading to be melamine polished/enamel painted as per color scheme. Cabinet will have flaps made of 18mm.thk. comm. ply board laminated from both faces,fixed with the help of SS Hinges and SS Handle as per approval/design. Use favicol S.H. for all joints. The work includes good quality S.S. hinges/albihari hinges, S.S. handle, cluthers, lock, bolts and hardware of approved quality etc complete. ( NON SOR)	Sqm	1.35
23. (NON	Providing and fixing roller blinds Vista/Mascot/ windowtech make and shade with hanging and drawing system including all hardware	Sqm	24



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

SOR)	and fixing complete. ( NON SOR)		
24.	Providing and fixing artificial synthetic green long and fine yarns grass, UV/water resistant with SBR latex backing eco-friendly durable high density 100 % PP ( Poly Poplin ) anti UV fiber.denier 12000 dtex, stich rate 18 stiches per 10cm, stich density 16800 stiches/m2, tufted weight 1830g/sqm approx. Roll size will be 25.00m X 2.00m (25mm thick)- weight 150kg- per roll.( SOR Item No. 11.86.1)	Sqm	5
25. (NON SOR)	WALL PAPER -Providing & fixing Wall paper on existing smooth surface of Wall/Panelling i/c applying of adhesive & Powder, fixing on wall and matching the Joints /Design pattern as per the approval of the Engineer In charge complete and nothing will be paid extra for execution of the item .This job includes all Leads, lifts for all floor, Material & labour complete and nothing will be paid extra for execution of the item. All work is to be executed as per the design approval and directions. Surface area will be measured for payment.(NON SOR )	Sqm	93
26.	Providing and fixing 12 mm thick toughened glass including all connectors and fixing accessories all complete for partitions, cubicals etc. As per direction of Engineer-in-Charge.( SOR Item No. 21.22)	Sqm	8.4
27. (NON SOR)	2 SEATER SOFA (SIZE 1340mmX675mmX seat height- 450 & seat back height-750mm)- S & F sofa made of 18mm thk. ply board fixed on frame work made of second class T.W.of cross section 50x50mm. Seat is provided with 18mm.tk. comm. ply & back is provided with 12mm plywood. Finished Hand rest is 575 mm.ht.from floor lvl., Seat Back is at 750mm. ht.from floor lvl. and Seat is at 450mm inclusive cushion. ht. from floor levle. as per Drg. Seat is covered with 100mm thk. U-foam (40 density) + 20mm thk. U-foam (40 density) covering it. Back & hand rest is covered with 40mm thk. U-foam (40 density) . Sofa with Internal seat size 550X550mm & back in sloping form and arm rest on both side as per drawing. Cushioned seat ,back hand rest and sides shall be be fully covered with upholstery cloth/leather finish of approved texture, color and shade including all fixtures, fasteners, nails, screw, ( NON SOR )	Nos.	2
28. (NON SOR)	Providing & Fixing of Planter of 450mm ht. & 400mm width as per design. Basic structure made up of 18mm thick commercial plywood Finished With 1.0mm thick laminate on exposed surfaces of plywood. This job includes all Leads, lifts for all floor, Material & labour complete and nothing will be paid extra for execution of the item. All work is to be executed as per the direction and approval of Engineer in charge. ( NON SOR)	Mt.	2.4
29.	Providing and fixing plywood 4 mm thick one side decorative veneer conforming to IS: 1328 (type-1) for plain lining / cladding with necessary screws, priming coat on unexposed surface with: Decorative veneer facings of approved manufacture. (SOR Item No. 9.32)	Sqm	36
30.	Mealamine polishing on wood work by preparing the surface applying putty base course. Prepare the surface smooth by sand papering and then applying Mealamine polish with air compressor. One or more coats on old work.( SOR Item No. 14.42.1)	Sqm	36



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

31.	Providing and fixing tufted 1/10" loop pile (carpet tile / Carpet). EN (European Standard) size 50cm x 50cm /roll Size of total thickness 5.5 mm and above with total mass of 4100g/m <sup>2</sup> approx and with polyester fleece primary backing with standard dimensional stability with impact sound / noise reduction and recommended for high traffic acoustical area. (SOR Item No. 11.89)	Sqm	93
32.	Providing & applying white cement based putty of average thickness 1mm of approved brand & manufacturer, like Birla White/JK white or equivalent over the plastered wall surface to prepare the surface even and smooth i.e. all cost of material labour and scaffold etc. in all position complete. (SOR Item no.- 13.41)	Sqm	250
33.	Wall painting with acrylic emulsion paint , having VOC ( volatile Organic Compound) content less than 50 grams/litre, of approved brand & manufacturer , including applying additional coats wherever required ,to achieve even shade and colour. Two coats. (SOR Item No. 13.50.2)	Sqm	250
34.	Providing and laying vitrified floor tiles Multi/Double charged (Minimum top layer thickness 2.0mm) Neno Polished self design, in different size with water absorption less than 0.05% and conforming to IS:15622 of approved make in all colours & shades, quality/premium quality in flooring laid on 12mm, thick cement mortar 1:4 (1cement :4sand) including grouting the joints with white cement and matching pigments etc. complete Size 800X1200 mm thickness 11-12mm (SOR No. 11.78.2.3)	Sqm	165
35.	Providing and laying gang saw cut 18 mm thick, mirror polished premoulded (wherever required) and pre polished machine cut granite stonework in flooring of required size shape of approved shade, color and texture in flooring laid over 20 mm thick base of cement mortar 1:4 (1 Cement: 4 sand) including grouting the joints with white cement mixed with matching pigments epoxy touch ups etc. complete as per direction of Engineer-in-Charge. Fine grained granite dark/Black/darkRed/White or equivalent with self design/pattern/crystals of other colors of glitter (SOR No. 11.29.1.1).	Sqm	24
36.	Granite work gang saw cut (polished and machine cut) of thickness 18mm for wall lining (veneer work), backing filled with a grout of average 12 mm thick in cement mortar 1:3 (1 cement: 3 sand) including pointing with white cement mortar 1:2 (1 white cement: 2 marble dust) with an admixture of pigment to match the marble shade: (To be secured to the backing by means of cramps, which shall be paid for separately). Fine grained granite dark Black/dark Red/ White or equivalent with self design/ pattern/crystals of other colors of glitter (SOR no. 11.28.1.1)	Sqm	91
37.	Providing and fixing stainless steel English (Capital) and Hindi letters in standard pattern bellow type made with 1.20 mm thick stainless steel . Depth of letter shall not be less than 30mm and rate includes welding/soldering of joints polishing, buffing and fixing on the wall beam surface at any height with necessary nut and bolts/fastener wherever is required complete as per direction of Engineer-in-charge. (SOR NO. 27.8)	Per Letter Per CM Height	950
38.	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering	Sqm	7.6



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	with vertical grains or cross bands and face veneers on both faces of shutter. 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.( SOR Item No. 9.18.1)		
39.	Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured). ( SOR Item No. 9.21)	Sqm	6.3
40.	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete: 300x16 mm ( SOR Item No. 9.57.1)	Nos.	4
41.	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : 250x10 mm( SOR Item No. 9.58.1)	Nos.	2
42. (NON SOR)	Dismantling of Existing sanitary fixture of washroom Sanitary fixtures wash basin -3Nos. Wc- 2 Nos. & Urinal- 2Nos etc. ( NON SOR)	Nos.	1
43	Providing and fixing white vitreous china extended wall mounting water closet of size 780x370x690 mm of approved shape including providing and fixing white vitreous china cistern with dual flush fitting, of flushing capacity 3 litre/6 litre (adjustable to 4 litre/8 litres), including seat cover, and cistern fittings, nuts, bolts and gasket etc complete (SOR No. 17.5)	Nos.	2
44	Granite stone work 18 mm thick of any colour in riser of steps, skirting, dado and pillars laid on 12 mm average thick cement mortar 1:3 (1 cement: 3 sand) and jointed with white cement slurry mixed with pigment to match the shade of slab.(SOR Item 11.33)	Sqm	4
45	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge.( SOR Item No. 18.6)		
	15 mm nominal outer dia .Pipes. ( SOR Item No. 18.6.2.1)	RMT	26
46.	Providing and fixing CPVC gate valve with knob of approved quality. ( SOR Item No. 18.13) 25 mm nominal bore ( SOR Item No. 18.13.1)	Nos.	2
47.	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors ( SOR Item No. 17.57.2) Sand cast iron S & S as per IS - 3989 ( SOR Item No. 17.57.2.1)	Nos.	5
48.	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS: 8931. 15 mm nominal bore. ( SOR Item No. 18.34)	Nos.	8
49.	Providing and fixing C.P. brass elbow operated pillar cock of approved quality and make conforming to IS: specification. 15 mm nominal bore. ( SOR Item No. 18.42)	Nos.	4
50.	Oval shape wash basin over counter /under counter (Counter to be paid separately). ( SOR Item No. 17.11.10)	Nos.	4
51.	Providing and fixing white vitreous china battery based infrared sensor operated urinal of approx. size 610 x 390 x 370 mm having pre and post flushing with water ( 250 ml and 500 ml consumption), having water inlet from back side, including fixing to wall with suitable brackets all as per manufacturers specification and direction	Nos.	2



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	of Engineer-in-Charge. (SOR Item No.17.10)		
52.	Providing and fixing on wall face unplasticised Rigid PVC soil and waste pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. Single socketed pipes for working pressure of 4 kg./cm <sup>2</sup> ( minimum wall thickness 3.2mm) ( SOR Item No. 17.58)		
	75 mm diameter ( SOR Item No. 17.58.1)	RMT.	14
	110 mm diameter ( SOR Item No. 17.58.2)	RMT.	8
53.	Providing and fixing unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC soil and waste pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS :5382 leaving 10 mm gap for thermal expansion. ( SOR Item No. 17.59) Bend 87.5° ( SOR Item No. 17.59.5)		
	75 mm bend ( SOR Item No. 17.59.5.1)	Nos.	10
	110 mm bend ( SOR Item No. 17.59.5.2)	Nos.	6
54.	Single tee with door ( SOR Item No. 17.59.3)		
	75x75x75mm ( SOR Item No. 17.59.3.1)	Nos.	3
	110x110x110 mm ( SOR Item No. 17.59.3.2)	Nos.	2
55.	Single tee without door ( SOR Item No. 17.59.4) 75x75x75 mm (SOR Item No. 17.59.4.1)	Nos.	4
56.	coupler ( SOR Item No. 17.59.1)		
	75 mm bend ( SOR Item No. 17.59.1.1)	Nos.	6
	110 mm bend ( SOR Item No. 17.59.1.2)	Nos.	4
57	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. For Extnal work. 25 mm dia. nominal bore ( SOR Item No. 18.7.3)	meter	15
58	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : With 20mm nominal size graded stone aggregate M 15 – Grade concrete. ( SOR Item No. 4.1.1.3)	Cum	1.5
59	Providing and fixing in position best Indian C. P. Brass made (0.3 micron Chrome and 10 micron Nickel plated) Toilet paper holder with Flap (SOR NO. 25.56)	Nos.	2
60	Providing and fixing bevelled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. (SOR NO. 17.67)	Sqm	2
61	Providing and fixing 18mm thick gang saw cut mirror polished (premoulded and prepolished) machine cut for kitchen platforms, vanity counters, window sills , facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement : 4 sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing moulding and polishing to edge to give high gloss finish wherever required etc. complete at all levels. Samples approved by Engineer-in Charge. ( SOR Item No. 11.22)		
	Granite fine grained dark crystal of other colours and various patterns. ( SOR Item No. 11.22.2.1)	Sqm	4
	Cuddpah stone. ( SOR Item No. 11.22.5)	Sqm	4





## MADHYA PRADESH POLLUTION CONTROL BOARD

**Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016**

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

62.	Extra for fixing marble /granite stone over and above corresponding basic item, in facia and drops of width upto 150 mm with epoxy resin based adhesive including cleaning etc. complete. (SOR Item No. 11.40)	RMT	6
63.	Providing and fixing CP brass waste coupling of approved quality and make for sink and wash basin.Waste coupling 38mm of 83mm length and 77mm breadth (SOR No. 17.71.2)	Nos.	2
64.	Providing and fixing CP brass bottle trap of approved quality and make for sink and wash basin. (SOR No. 17.72)	Nos.	2
65.	Providing and fixing in position best Indian C. P. Brass made (0.3 micron Chrome and 10 micron Nickel plated) Single Towel Rail 600 mm long. (Premium Range) (SOR NO. 25.50)	Nos.	2
66.	Providing and fixing in position best Indian C. P. Brass made (0.3 micron Chrome and 10 micron Nickel plated) Soap Dish Holder. (SOR NO. 25.53)	Nos.	2
67.	Providing and fixing in position best Indian C. P. Brass made (0.3 micron Chrome and 10 micron Nickel plated) Soap Dispenser with Metallic Bottle. (SOR NO. 25.54)	Nos.	2
68.	Providing & Fixing of CP Brass Urinal spreader of approved quality and make (SOR NO. 17.76)	Nos.	2
69.	Providing and fixing in position best Indian Health Faucet with 8mm dia 1 meter long Flexible Tube and wall bracket with N. R. V. (non-return wall) (SOR NO. 25.37)	Nos.	2
70.	Providing & Fixing 8mm thick frosted Urinal glass partition size 900x450mm brass made bracket (SOR NO. 25.62)	No.	1
71 (NON SOR)	Providing and Placing of RECTANGULAR WORKSTATION / Linear Workstation Panel Base of Size: 1200mm(W) x 600mm(D) Having 25 mm thick Worktop with PVC lipping & 3 Drawer Metal Pedestal , keyboard and cpu trolley : 54 mm thick Modular Partition Panel of 1200mm height Panel. Panel based Modular Workstations of 54 mm thickness with extruded aluminum end post of size 54x16.5mm with continuous vertical locking arrangement for interconnection of two adjacent panels. Top trim is of aluminum section of size 54x12mm and snap fitted on its base of size 54x20mm. The aluminum frame work is supported on lower and upper partition block. Bottom Block is made up of 9mm prelaminated particle board of desired shade which is pasted On 33x25mm thick particle board batton frame, which is properly screwed to end post and Bottom electrical race way. Upper block is fixed above the table top and is made up of particle battons fixed with 9 mm thick pin board and cloth of desired shade, Optionally White Board or Glazing can Be provided instead of pin board. Raceway- one bottom raceway is provided as standard for drawing wires along the width of panel. The raceway is covered with aluminum extruded plates from both sides and snap fitted with aluminum extruded raceway clip. The modular switch & socket plates can be mounted & punched onto the raceway panels with easy cable connectivity & accessibility in case of any repairs etc. Top rails, end posts, connectors & raceway panels are made out of aluminum duly powder coated after 7 tank anti-rust phosphate treatment. All horizontal Top rail & vertical end post profiles would be elegantly	Nos.	24



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	curved in a convex fashion with a lengthwise running groove in the middle. Make - Godrej, Methodex, Herman miller (NON SOR Item)		
72 (NON SOR)	Medium Back Chair Made Of Good Quality . Seat Plywood Made Of 12mm Hot Pressed . Upholstery PVC Structure Moulded With Prime Quality High Stretch Knitted Polyester Fabric . PHA ( Gas-Lift ) 85mm (TDC 152mm & BDC 67) . Seat & Back Are Firmly Connected To The Base Frame Mechanism Moves In The Ratio 1:2. Mechanism Provided Upright Position Locking . Chair Max Height 1010 & min Height 925 . 470W x 480D Base Seat 60mm Thick Moulded With PU Foam & 510W x 510H Back Seat 60mm Thick Moulded With HD Foam . Tilt Adjustment Can Be Operated In Seating Position . 220x500/640 Arm Rest Fitted To The Seat With Armrest Connecting Brackets . Armrest Should Be Injection Moulded From Black Nylon . Height From Seat To Ground 450mm . Seating Height Can Be Adjusted With a Pneumatic Gas Lift . Pedestal Pitch Centre Dia 665mm Without Casters . Casters Made Of Moulded Black Nylon Metal Bolt Inserted & Fitted With 5 Nos . Twin Wheel Casters 50mm Dia . Pedestal Pitch Centre Dia 665mm Without Casters . Make - Godrej, Methodex, Herman miller (NON SOR Item)	Nos.	24
73	Brick work with well burnt chimney bricks in bulls patent trench kiln manufactured by ghol process, crushing strength not less than 40kg/cm <sup>2</sup> and water absorption not more than 15% in superstructure above plinth level and up to floor two level i/c curing etc. complete. Cement mortar 1:4 (1 cement: 4 sand) (SOR Item No. 6.2.1)	Cum	4.0
74	15 mm cement plaster on the rough side of single or half brick wall of mix 1:6 (1 Cement : 6 sand) (SOR Item No. 13.2.2)	Sqm	42
<b>ELECTRICAL WORK</b>			
75	Supply and laying of XLPE Insulated power cable (confirming IS-7098 Part-I ) 1100 Volt grade, 3½ core 35 Sq.mm. ISI MARKED with Alu. Stranded /solid conductor. (SOR Item No. 41.1.7.2)	M	250
	4 core unarmoured 16 sq. mm. (SOR Item No. 41.1.9)	M	100
76	Supplying of approved make TPN MCB DB metal double door IP 43 protection with provision for FP MCB/ Isolator/ RCCB/ RCBO as incomer and SP MCBs as outgoing inclusive of busbar, neutral bar, earth bar, connection copper wire not less than 16 sq.mm & two earth terminals etc. complete as per IS:13032(exclusive of MCB & isolator): (SOR Item No. 27.12)		
	4 Way (4+12) (SOR Item No. 27.12.1)	No.	1
	8 Way (8+24) (SOR Item No. 27.12.4)	No.	1
77	Supply of ISI marked and accepted standard of miniature circuit breaker (MCB) of 'C' series with short circuit indication, suitable for 240/415 Volts,50 Cycle, 10 kA/15 kA Value AC supply conforming to IS : 8828 : 1996, IEC : 60898 :2002 & 60947-2 but without enclosures :- (SOR Item No. 27.8)		
	SINGLE POLE (SP) MCB SP 6Amp to 32Amp 10kA rating (SOR Item No. 27.8.1.2)	Nos.	36
	For Triple pole (SOR Item No.27.8.3) MCB TP For 40Amp 10kA rating (SOR Item No.27.8.3.3)	Nos	1
	Four pole MCB FP 50Amp to 63 Amp 10kA rating( SOR Item	Nos.	1



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	No.27.8.4.4)		
78	Supplying and drawing following pair of 0.5 mm size solid annealed copper conductor PVC Insulated telephone cable as per DOT Specifications in existing surface / concealed steel / PVC Conduit / Cassing-N-Capping as required. ( SOR Item No.38.2)		
	2 Pair ( SOR Item No.38.2.2)	Mt	250
	10 pair ( SOR Item No.38.3.3)	Mt.	70
79	Supply, Installation testing and commissioning of telephone Tag block Krone connector with enclosure and lock complete as mentioned below :- 10 pair ( SOR Item No.38.4)	Nos.	1
80	Supplying, erecting and testing of approved make 300 mm sweep Exhaust Fan heavy duty with mounting frame, blades AC 230-250 complete connection and including, frame bolt/ Anchor hole fastners etc. complete finished of approved as required. (SOR item no.30.6.1)	Nos.	2
81 (NON SOR)	Supply , Installation , testing and commissioning of Factory made 1.4HDMI Cable along with Connectors.(15mtr length) Make- MX / Dyeton/Terabyte ( NON SOR Item )	Nos.	2
82 (NON SOR)	Supply , Installation , testing and commissioning of Factory made VGA along with Connectors.(15mtr length) Make- MX / Dyeton/Terabyte ( NON SOR Item )	Nos.	2
83 (NON SOR)	Supply , Installation , testing and commissioning of Factory made RCA along with Connectors.(15mtr length) Make- MX / Dyeton/Terabyte ( NON SOR Item )	Nos.	2
84	Supply and fixing of recessed mounting type Led light fixture, LED of 1 to 3 Watt each assembled on single MCPCB, having color temp upto 6500K & having 50000 burning hrs life with minimum @ L 70, system lumen output should be minimum with efficacy>100 lm/Watt. LED driver PF> 0.95, THD < 20% & surge protection 4KV. The colour rendering index of LED light should be more than 70. Housing made of CRCA powder coated frame with glare free diffused polycarbonate cover. Submission LM 79-08/IS16106 (2012), IEC60598, IEC61347i/c connection wire, testing etc. to complete the job. ( SOR Item No. 31.4) LED luminiare 2' X 2', 36Watt, color temp 3000- 6500k as required. ( SOR Item No. 31.4.1 ) Make philips ,syska, bajaj	Nos.	22
85	Supply and fixing recessed mounting LED down lighter, LED of 1 to 3 Watt each assembled on single MCPCB, having color temp upto 6500K & having 50000 burning hrs. life with minimum @ L 70, system lumen output should be minimum with efficacy>100 lm/Watt. LED driver PF > 0.95, THD < 20% & surge protection 4KV. The colour rendering index of LED light should be more than 70. Housing made of pressure die cast aluminium/CRCA powder coated frame with glare free diffused polycarbonate cover. Submission LM 79-08/IS16106 (2012), IEC60598, IEC61347i/c connection wire, testing etc. to complete the job.( SOR Item No. 31.6 )		
	14/15 Watt, color temp 3000-6500k as required.( SOR Item No. 31.6.5 )	Nos.	37
86.	Point wiring (excluding metallic switch box & sheet but including		



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	switches, sockets, lamp holders/ceiling roses etc) with 1.5sq. mm. PVC insulated cable FRLS with copper multi strand conductor ISI marked in concealed rigid P.V.C. Conduit (HMS) ISI marked of suitable size and 1.5sq. mm. PVC insulated FRLS copper earth continuity conductor of green colour inside conduit, screwless connector for joints etc. as required as per specification for :- (Using modular accessories) ( SOR Item No. 4.1 ) Light point/fan points. ( SOR Item No. 4.1.1 )		
	Primary Short point ( SOR Item No. 4.1.1.1 )	Nos.	12
	Primary Medium point ( SOR Item No. 4.1.1.2 )	Nos.	26
	Primary Long point ( SOR Item No. 4.1.1.3 )	Nos.	27
87	(Light point/fan points) looping point ( SOR Item No. 4.1.2 )		
	Secondary Short point ( SOR Item No. 4.1.2.1 )	Nos.	30
88	3 Pin 6 Amp socket outlet on Separate Board ( SOR Item No. 4.1.3 )		
	Short point ( SOR Item No. 4.1.3.1 )	Nos.	12
	Medium point( SOR Item No. 4.1.3.2 )	Nos.	23
	Long point ( SOR Item No. 4.1.3.3 )	Nos.	33
89	Point wiring (excluding metallic switch box & sheet but including switches, sockets) for 3 pin 6 amp socket outlet point with 1.5 Sq.mm. PVC insulated cable FR with copper multi strand conductor ISI marked in concealed rigid PVC conduit (HMS) ISI marked of suitable size and 1.5 Sq. mm PVC insulated copper earth continuity conductor of green colour inside conduit with required materials as per specification on same board. ( SOR Item No. 4.2 )	Nos.	54
90	Wiring for circuit wiring with PVC insulated cable FR with copper multi strand conductor ISI marked in concealed rigid P.V.C. conduit (HMS) of ISI marked suitable size etc. as required as per specification ( SOR Item No. 4.3 )		
	2x2.5 Sq.mm.( SOR Item No. 4.3.1 )	M	90
	4x2.5 Sq.mm.( SOR Item No. 4.3.2 )	M	60
	6x2.5 Sq.mm.( SOR Item No. 4.3.3 )	M	40
	8x2.5 Sq.mm.( SOR Item No. 4.3.4 )	M	30
91	Point wiring (excluding metallic switch box & sheet ) for 3 Pin 16 Amp. Socket Outlet Point With 4 Sq. mm. PVC insulated cable FR with copper multi strand conductor ISI marked in Concealed rigid P.V.C Conduit (HMS) ISI Marked of suitable size etc. with 16 Amp. F.T. Switch & Socket / S.S.Combined 6/16 Amp. of ISI Marked and 4 Sq.mm. PVC insulated copper earth continuity conductor of green colour inside conduit as per specification for :- On Separate Board ( SOR Item No. 9.1.1 )		
	Short Point	Nos.	2
	Medium Point	Nos.	4
	Long Point	Nos.	6
	Extra Long -I	Nos.	2
	Extra Long -II	Nos.	2
	Extra Long -III	Nos.	2
92	Same board switch socket 6/16 Amp ( SOR Item No. 9.2 )	Nos.	8
93	Supplying and fixing PVC conduit ISI marked alongwith the accessories in concealed system including painting etc. as		



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	required. ( SOR Item No. 16.1 )		
	PVC Conduit 20mm (HMS) ( SOR Item No. 16.1.1)	Mt.	150
	PVC Conduit 25mm (HMS) ( SOR Item No. 16.1.2)	Mt.	120
	PVC Conduit 32mm (HMS) ( SOR Item No. 16.1.3)	Mt.	25
94	Supplying, erection and testing of approved make 400 mm sweep Wall Mounting fan complete with Wall Bracket ,canopy, blades, speed Regulator etc .A.C 230-250 volts with connections and including raw bolt/Anchor hole fastener etc. complete finished of approved as required. ( SOR Item No. 32.2.2 )	Nos.	10
95	Supplying and drawing single core PVC insulated cable FR with copper multi strand conductor ISI marked in existing rigid PVC Casing-N-Capping / conduit in surface or concealed as per specification. ( SOR Item No. 19.1 )		
	(a) 1 X 1.5 sq mm ( SOR Item No. 19.1 .1.1)	Mt.	80
	(a) 1 X 2.5 sq mm ( SOR Item No. 19.1.2.1)	Mt.	70
	4.00 sq. mm. wire , 1 X 4.00 sq. mm. ( SOR Item No. 19.1.3.1 )	Mt.	75
	6.00 sq mm wire , 1 X 6.00 sq mm ( SOR Item No. 19.1.4.1 )	Mt.	40
96	Wiring for sub-mains with PVC insulated cable FRLS with copper multi strand conductor ISI marked in recessed/concealed rigid PVC conduit (HMS) FRLS ISI marked of suitable size (conduit included) including 2mm thick accessories, connection etc, as required as per specification. (Refer General Notes for Classification of Conduit Wiring Point No.11) (SOR Item No. 23.1)		
	4 WIRE SUB-MAIN ( SOR Item No. 23.1.4) 6.0 sq. mm. cable (SOR Item No. 23.3)	Mt.	30
97	Supply and fixing Led tube rod comprising of LED tube with non-integral/integral driver, upto 6500K color temp having 40000 burning hrs life with minimum @ L 70, system lumen output should be minimum with system efficacy> 100 lm/Watt. LED driver PF> 0.95 & THD < 20%. The colour rendering index of LED light should be more than 70. Submission LM 79-08/IS16106 (2012), IEC60598, IEC61347 i/c connection wire, testing etc. to complete the job. ( SOR Item No. 31.3)		
	Tube light LED 1 X 18Watt, Integral i/c batten aluminium body, PC diffuser. ( SOR Item No. 31.3.3)	Nos.	10
98	Labour charges for fixing sheet steel enclosure, MCB DB surface mounting type, as per accepted practice on 25x5mm flat iron clamp duly embedded in wall, cable connection etc. complete. ( SOR Item No. 28.5)		
	FOR S.No :- 27.12.3 to 27.12.4 & 27.13.1 ( SOR Item No. 28.5.3)	Nos.	02
99	supplying and drawing Co-axial T.V. Cable RG-6 Grade , 0.7 mm Solid Copper conductor PF Insulated , Shielded with fine tined copper braid and protected with PVC Sheathed in the existing surface / concealed ,steel / PVC. Conduit as required. ( SOR Item No. 38.1)	meter	50
100	Supply, fixing and testing of T.V. Outlet F.T ( SOR Item No. 38.7)	Nos.	1
101	Supply, fixing and testing of T.V. Outlet Modular (1Module) ( SOR Item No. 38.8)	Nos.	1
102	Supplying and fixing PVC Casing-N-Capping (Double Fold) ISI Marked along with accessories on surface etc. as required ( SOR		



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	Item No. 17.1)		
	PVC Casing-N-Capping (Double Fold) 38 mm x 20mm ( SOR Item No. 17.1.4)	meter	20
	PVC Casing-N-Capping (Double Fold) 32 mm x 12mm ( SOR Item No. 17.1.3)	meter	30
	PVC Casing-N-Capping (Double Fold) 25 mm x 12mm ( SOR Item No. 17.1.2)	meter	50
	PVC Casing-N-Capping (Double Fold) 20 mm x 12mm ( SOR Item No. 17.1.1)	meter	60
103	Supplying and fixing of approved make modular type PVC box minimum depth 40mm and minimum thickness 2mm with modular base and cover plate including fixing on surface etc. as required for:- ( SOR Item No. 18.3)		
	1 or 2 Module ( SOR Item No. 18.3.1)	Nos.	4
	3 Module ( SOR Item No. 18.3.2)	Nos.	63
	6 module ( SOR Item No. 18.3.4)	Nos.	33
	8/9 Module ( SOR Item No. 18.3.5)	Nos.	5
	12 Module ( SOR Item No. 18.3.6)	Nos.	4
	16 module ( SOR Item No. 18.3.7)	Nos.	1
104	Supply, fixing and testing RJ11 Telephone jack single with shutter F.T ( SOR Item No. 38.7)	Nos.	9
105	Supply , fixing and testing of RJ- 11 telephone jack modular ( 1 module ) (SOR Item No. 38.8)	Nos.	9
106	Supply, installation testing and commissioning RJ-45 computer jack cat 6 with shutter modular( 1 module) ( SOR Item No. 38.9)	Nos.	34
107	Supplying and drawing 4 pair shielded, 0.5 mm PVC. Insulated copper conductor un-armoured Cat-6 computer cable FR in Existing surface / concealed, steel / PVC. Conduit/Casing-N capping as required.(Elec .SOR Item 38.11)	meter	650
108	12U cabinet 600X600X500, wall mounting with 6 point 5 Amp. socket power supply strip and fan, tray. ( SOR Item No. 38.18.3)	Nos.	1
109	CAT 6 RJ45 Patch Cord F/UTP 2 Mtr. ( SOR Item No. 28.14.2)	Nos.	34
110	CAT 6 RJ45 Patch Cord F/UTP 1 Mtr.( SOR Item No. 38.14.1)	Nos.	36
111	Supply, installation testing and commissioning of 19" modular patch - 1 U patch panel 24, RJ 45 cat-6 connector ( SOR Item No. 38.16)	Nos.	2
112	24 port PoE switch with 4 SFP ports Supply, installation testing and commissioning of 24 port PoE switch with 4 SFP ports, having security features like port security supports 64 MACs per port, auto surveillance VLAN, loopback detection automatically disables a port when a loop is detected, cable diagnostics allows administrators to determine cable status, UTP Cat. 5, Cat. 5e (100 m max.), full/half-duplex for 10/100 MBPS, full-duplex for 1000 MBPS, auto MDI/MDIX adjustment for all twisted-pair ports, switching capacity, 56 GBPS, maximum 64 bytes packet forwarding rate, 41.7mbps, Ports 1 to 24 compliant with 802.3 at ( SOR Item No. 54.28.1)	Nos.	2
113 (NON SOR)	Dismantling and Re-installation of Split Air conditioners with suitable , gas charge and hole packing all complete work. ( NON SOR Item)	Nos.	2
114	Cassette AC :- Supply installation testing and commissioning of		



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	split type ceiling cassette Slim line/floor standing air conditioning unit of capacity including indoor, outdoor unit fitted with rotary compressor, copper condenser and first charge refrigerant R410A/eco friendly green gas only, cordless remote control, auto air swing louvers, connection copper lead wire between outdoor and indoor unit, connection copper lead wire upto 1.5 mtr., excluding connection copper pipe of required size, insulation, floor stand for outdoor unit, condense water outlet complete etc as required. Outdoor/indoor units should be of same make (brand). (SOR Item No. 46.13) Ceiling suspended/mounted cassette type 4 way unit with inbuilt drain pump & decorative panels. (SOR Item No. 46.13.1)		
	1.8 TR/2.0 TR single phase (SOR Item No. 46.13.1.1)	Nos.	7
115	Supply, installation, testing & commissioning of suction/discharge copper pipe line in split air conditioning unit 1.0/1.5 TR/2 TR/3 TR capacity including brazing, nitrile rubber insulation 6/9mm thick class 'O', etc complete as required. (SOR Item No. 46.3)		
	Copper tube 1/4" (SOR Item No. 46.3.1)	Meter	125
	Copper tube 3/8" (SOR Item No. 46.3.2)	Meter	125
	Copper tube 1/2" (SOR Item No. 46.3.3)	Meter	125
	Copper tube 5/8" (SOR Item No. 46.3.4)	Meter	125
116	Drain piping :- Providing and fixing of CPVC, 6Kg/cm <sup>2</sup> drain water piping with fittings, support and insulated with 6 mm thick closed cell elastomeric nitrile rubber insulation complete as per specification. (SOR Item No. 46.31)		
	20 mm dia ID (SOR Item No. 46.31.1)	meter	70
	25 mm dia ID (SOR Item No. 46.31.2)	meter	35
117	<b>providing and installation of wireless public address systems with following units and specifications: ( NON SOR Item )</b>		
118	i) Host Unit - Carrier Frequency 2.4 GHz( 2400-2483MHz) Adaptive Digital FHSS Technology. Operating Range upto 40 meters. Frequency Response 70-15000Hz. Power Supply 12V DC from AC Adapter. Host unit should be used together CWS-8100C Chairman Unit, CWS- 8200D Delegate Units and GN- 45 Gooseneck Microphones. make Ahuja/Bosch/Classico	No	1
119	ii) Chairman Unit with free/ Request Mode Selection. Priority Function to override all Delegates.LCD Displays the working status and battery charge status. Microphone indicator Ring LED. Power supply 2 pcs, AA, Alkaline Batteries.	Nos.	1
120	iii) Delegate Unit with power/ Talk Button. LCD Displays the Delegate Unit No. and battery charge status. Microphone indicator Ring LED. Power Supply 2 pcs, AA Alkaline Batteries.	Nos.	14
121	iv) PA Ceiling Speaker (10W RMS) with an elegant , aesthetically pleasing rimless design. Excellent sound quality combined with an ultra-modern low profile appearance makes this ideally suited for high- end offices, restaurants, bars, malls etc.6" Full Range Speaker with power taps of 10/5/2.5W. 10 Watts continuous power handling capacity. Easy mounting with spring loaded wing clamps. 100V operation with easy selection of power taps through a terminal block. CSX-6101T	Nos.	6
122	v) Medium wattage PA Mixer Amplifier (160 watts with built-in digital player). Built -in MP3 player with remote control for USB, SD/MMC	No.	1



## MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

	card reader. Preamplifier and line Output for connecting to a Booster Amplifier and for recording the programme. Line input for connecting the output from any external mixer or permitting SSA-160DP to be used as a Booster power Amplifier. Resettable circuit breaker for protection against overload and short circuit. Instant transfer to DC power (car battery) if AC power fails. Box speaker/ Driver Unit selector switch. Bass boost defeated at Driver Unit position for safer operation of driver units. 5 LED array for output level monitoring. SSA-160DP		
--	--	--	--

Having examined the tender document with respect to form of contract, schedule of quantities, relating to the above mentioned work and having visited and examined the site of the proposed works and having acquired the requisite information relating thereto as affecting the tender invited by you on behalf of the M. P. Pollution Control Board. I/we undertake to complete and deliver the whole of the works within four months from the date of commencement of work as per the relevant clause of the contract. Upon receiving possession of the site, I/we shall be under obligation to pay the sum as per General Conditions of the contract. I/we have deposited earnest money of Rs 1,26,255.00 (Rupees One Lac twenty six thousand two hundred fifty five only) online on the portal and scanned copy of the same is uploaded as a proof.

Yours faithfully  
Name & Seal of the Partner of the firm





# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

Annexure-“2”

**Tender Notice No. MPPCB/HO/Maint./TS/01/2021-22**

## CHECK LIST

**Name of Work: Renovation of Conference Hall and Other work at MPPCB, Bhopal**

Description	Page No.
Name of the firm with Name of Contact Person	
Address of the firm with Telephone No, Fax No. Mobile No. and e. mail address	
List of permanent employees for work execution such as Project Manager, Site Engineer (Civil/Electrical), Supervisor with their contact mobile number (Copy attached)	
Details of Earnest Money Deposited (Scanned copy submitted)	
Documents indicating the set up of organization, Partnership, Proprietorship, Pvt. Ltd, public ltd. etc., (Copy Attached)	
Document related to Valid Enlistment with MPPWD/CPWD/MES/Railways/Public Sector Undertakings, other Government bodies etc. (Copy Attached)	
PAN No. (Copy Attached)	
Details of works of similar nature carried out in Central or State Government bodies/departments, Public Sector Undertakings (if any). (Copy attached)	
Copy of Registration with Employees Provident Fund Organization (if any). (Copy attached)	
GST Registration No. (Copy attached)	
Turn Over Certificate for last three F.Y. duly certified by CA (Copy attached)	
Undertaking regarding not being blacklisted in any Government Department	
Bank Name, Account Name, Account Number, Account Type, Branch IFSC Code (Copy attached)	

I/We agree to provide photocopy services in accordance with the Terms & Conditions given in Tender Document. In case, non submission of any of the above document or as described in the tender document, the offer submitted by me/we shall be treated as rejected.

(Signature of Bidder)  
With stamp



# MADHYA PRADESH POLLUTION CONTROL BOARD

Paryavaran Parisar E-5, Arera Colony, Bhopal – 462016

Phone (0755) 2466 191, E-mail [it\\_mppcb@rediffmail.com](mailto:it_mppcb@rediffmail.com) web [www.mppcb.mp.gov.in](http://www.mppcb.mp.gov.in)

## MAP OF WORK STATION

